





KERB AND CHANNEL (K&C)

(Typical reinstatement to apply to all profiles)









NOTES

- 1) CONCRETE SHALL BE F'c 25MPa AT 28 DAYS.
- 2) EXPANSION JOINTS TO BE PROVIDED 1m EITHER SIDE OF VEHICLE CROSSINGS, 1m EITHER SIDE OF CENTRE OF TREES AND EVERY 20m MAX SPACING.
- 3) ALL DIMENSIONS IN MILLIMETRES
- 4) CONCRETE TO BE VIBRATED TO ENGINEERS SATISFACTION. TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG (25kg) FOR EVERY CUBIC METRE OF CONCRETE.
- 5) KERB AND CHANNEL MACHINE MAY BE USED AT DISCRETION OF THE ENGINEER.
- 6) TRAFFIC CONTROL MUST BE IN ACCORDANCE WITH A.S.1742.3
- 7) IN ACCORDANCE WITH THE ROAD MANAGEMENT ACT '04 THE RE-INSTATEMENT WORKS MUST BE MAINTAINED BY THE RLEVANT SERVICE AUTHORITY FOR A PERIOD OF 12 MONTHS. PRIOR TO THE 12 MONTH PERIOD, COUNCIL WILL NOTIFY THE RELEVANT SERVICE AUTHORITY OF ANY RECTIFICATION WORKS REQUIRED.

*N.B - A further 12 month maintenance period will then apply to the identified rectification works.

Yarra Standard: YSD1103 Drawing Title:

REINSTATEMENT WORKS
CONCRETE KERB AND CHANNEL
SECTIONS

	Scale at A4 N.T.S		
	REV	DATE	DRAWN BY
	Α	22/08/90	CV
	В	12/04/05	CV
	С	26/11/12	SM



Richmond Town Hall 333 Bridge Road Richmond PO Box 168 Richmond 3121 Phone (03) 9205 5010 Fax (03) 8417 6666