

GENERAL NOTES

- 1. CONCRETE SHALL BE F'c 25 MPa AT 28 DAYS AND SHALL BE IN ACCORDANCE WITH THE CITY OF YARRA CONCRETE SPECIFICATION.
- CONCRETE TO BE VIBRATED TO ENGINEER'S SATISFACTION. TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG (25KG) FOR EVERY CUBIC METRE OF CONCRETE.
- 3. BLUESTONE BLOCKS (PITCHERS) ARE NOMINALLY 300x255x150mm.
- 4. THIS DRAWING TO BE READ IN CONJUNCTION WITH COUNCIL SPECIFICATION "CONSTRUCTION OF PITCHER KERB AND CHANNEL AND PRAM CROSSINGS".
- 5. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES UPON ARRIVAL TO SITE.
- 6. DAMAGED AND UNSUITABLE PITCHERS TO BE REPLACED.
- 7. THE NEED FOR AN A.G. PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.

Yarra Standard: YSD303 Drawing Title:

PITCHER KERB WITH COLOURED CONTRETE TRAY

Scale at A4 N.T.S				
	REV	DATE	DRAWN BY	
	Α	29/11/07	HL	
	В	30/04/12	DKC	
	С	04/10/13	OK	
				C



Richmond Town Hall 333 Bridge Road Richmond PO Box 168 Richmond 3121 Phone (03) 9205 5010 Fax (03) 8417 6666