

GENERAL NOTES

- 1. PITCHERS ARE NOMINALLY 300*225*150mm.
- 2. WHEN RECONSTRUCTING EXISTING BLUESTONE KERB & CHANNEL THE NUMBER AND PATTERN OF BLUESTONE IS TO MATCH THE ORIGINAL DETAIL. WHEN CONSTRUCTING NEW BLUESTONE KERB AND CHANNEL, BLUESTONE MUST BE LAID IN A PATTERN CONSISTENT WITH THE SURROUNDING AREA (OR AS DIRECTED BY THE ENGINEER)
- 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH COUNCILS SPECIFICATION " CONSTRUCTION OF PITCHER KERB & CHANNEL AND PRAM CROSSINGS".
- 4. DAMAGED AND UNSUITABLE BLUESTONE BLOCKS(PITCHERS) TO BE REPLACED
- 5. ALL BLUESTONE JOINTS TO BE NO MORE THAN 15mm WIDE.
- 6. ALL MORTAR JOINTS TO HAVE A BRUSH FINISH
- 7. CEMENT TREATED CRUSHED ROCK BEDDING BELOW THE SHALL HAVE A MINIMUM COMPACTED DENSITY OF 90% OF THE CHANNEL MODIFIED AASHO VALUE. CEMENT TREATED CRUSHED ROCK IN FRONT OF THE CHANNEL SHALL HAVE A MINIMUM COMPACTED DENSITY OF 95% OF THE MODIFIED AASHO VALUE.
- 8. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER.

Yarra Standard: YSD308 Drawing Title:

PITCHER KERB WITH TWO & HALF PITCHER CHANNEL

Scale at A4 N.T.S			
REV	DATE	DRAWN BY	.1
Α	27/11/07	HL	الأع
В	30/04/12	DKC	
С	30/04/13	EP	
D	04/10/13	OK	CITY OF
			W DD
			I YAKK
			TOTAL

Richmond Town Hall 333 Bridge Road Richmond PO Box 168 Richmond 3121 Phone (03) 9205 5010 Fax (03) 8417 6666