



## **GENERAL NOTES**

- 1. CONCRETE TO BE F'c 25MPa AT 28 DAYS, TO BE CHARCOAL COLOUR AT THE RATIO OF 1 BAG(25KG) FOR EVERY CUBIC METER OF CONCRETE.
- 2. DRESSED KERB ARE NOMINALLY 1500\*300\*300mm
- 3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH COUNCILS SPECIFICATION "CONSTRUCTION OF PITCHER KERB AND CHANNEL AND PRAM CROSSINGS"
- 4. CEMENT TREATED CRUSHED ROCK TO BE LAID WITHIN 15 MINUTES UPON ARRIVAL OF SITE
- 5. DAMAGED AND UNSUITABLE BLUESTONE BLOCKS (PITCHERS) TO BE REPLACED
- 6. THE NEED FOR AN A.G PIPE TO BE DETERMINED BY CONTRACT SPECIFICATIONS OR SUPERVISING ENGINEER

## Yarra Standard: YSD318 Drawing Title:

DRESSED KERB WITH COLOURED CONCRETE TRAY

Scale at A4 N.T.S			9-2
REV	DATE	DRAWN BY	
Α	27/11/07	HL	-9/6x
В	30/04/12	DKC	
С	04/10/13	OK	المرتبير)
			CITY OF
			T/DDA
			⊢ YAKKA -

Richmond Town Hall 333 Bridge Road Richmond PO Box 168 Richmond 3121 Phone (03) 9205 5010 Fax (03) 8417 6666